

- 1: Clean areas of dirt, weeds, mud with street sweeper, power broom and/or power blowers and truck material off site.
- 2: Crack fill ¼" or more cracks with all rubberized crack filler, no sand, gravel, asphalt, etc.
- 3: Separate quote on patching for areas marked by owner.
- 4: Apply two (2) coats Seal Master Sealer **on separate days** with 3 pounds of sand; 75% sealer, 25% water.
- 5: An inspector will be on site to verify compliance while work is being done.
- 6: *Preferably work should be done on the weekends (weather permitting) or by alternate arrangements made with the Director of Technology and Operations.*

All work must be completed June 26 - July 25, 2021.

Areas to be seal coated are as follows:

High School North Side (includes recessed area at rear of building)

Roadway between stadium and east end of high school

High School West lot

High School South lot

Middle School and Board of Education Main Parking lot including access roadway from Cedar Rd

Middle School South Lot

Roadway between Middle School and High School

Lindsey Elementary School-north end parking lot including area adjacent to N-1 entry and roadway at front of building

Westwood Elementary School-all lots (does not include playground)

Contractor responsible for measuring all square footages to assure compliance with above areas as described.

Successful bidder must provide current Workers Compensation Certificate and proof of Liability Insurance

Sealed bids are to be postmarked to West Geauga Local Schools, 8615 Cedar Road, Chesterland, OH 44026 (Attn: Treasurer) no later than April 19, 2021.

For any questions, contact Sean Whelan, Director of Technology and Operations at sean.whelan@westg.org or 440-729-6803.